





KITCHEN EQUIPMENT		
ITEM	DESCRIPTION	STATUS
1	5 WELL REFRIGERATED DROP-IN	N.I.C.
2	6 WELL HOT DROP-IN	N.I.C.
3	5 WELL HOT DROP-IN	N.I.C.
4	PROTECTOR GUARD	N.I.C.
5	DROP-IN HEATED SOLID PIZZA TOP	N.I.C.
6	DOUBLE SECTION PASS-THRU REF.	N.I.C.
7	ROLL-IN REFRIGERATOR	N.I.C.
8	COLD PAN	N.I.C.
9	PASS THRU REF.	N.I.C.
10	HOT HOLDING CABINET	N.I.C.
11	CASH REGISTER	N.I.C.
12	STAINLESS STEEL COUNTER	N.I.C.

- KITCHEN EQUIPMENT NOTES:**
- ALL EQUIPMENT SHOWN N.I.C. SHALL BE PURCHASED AND DELIVERED TO THE SITE BY THE OWNER. ALL UTILITIES AND SERVICES TO EQUIPMENT ARE IN CONTRACT. GENERAL CONTRACTOR TO COORD. INSTALLATION W/ OWNER. MOVEMENT OF ALL EQUIP. AFTER DELIVERY WILL BE BY CONTRACTOR, INCLUDING MOVING TO SETTING LOCATION.
 - FIELD VERIFY ALL DIMENSIONS SHOWN ON PLAN.
 - GENERAL CONTRACTOR, PLUMBING, ELEC. AND MECH. SUB-CONTRACTORS SHALL COORD. ALL PIPING, DUCT AND ELEC. REQUIREMENTS W/ ANY OTHER FURNISHED EQUIPMENT PRIOR TO RUNNING CIRCUITS, PURCHASING BREAKERS OR DEVICES & VALVES.
 - WHERE GAS EQUIPMENT IS PROVIDED, CONTRACTOR SHALL FURNISH AND INSTALL ALL NECESSARY VALVES AND REGULATORS.
 - AFTER INITIAL DELIVERY AND APPROXIMATE LOCATING OF EQUIPMENT, THE CONTRACTOR SHALL MOVE EQUIPMENT AS NECESSARY FOR FINAL CONNECTIONS AND OPERATING LOCATIONS.
 - FLOOR SHALL SLOPE TO DRAINS, STEEP SLOPES ARE NOT ACCEPTABLE. COORDINATE SLOPES WITH ARCHITECT.

DRAWING ISSUE RECORD		
DATE	REVISIONS	NO.
02/04/2020	SENT TO GUINNETT CO.	1
	ISSUE TO BID	



FINISH SCHEDULE				
NO.	FLOOR	BASE	WALLS	CEILING
F1	QUARRY TILE, MATCH EXIST'G	QUARRY TILE, MATCH EXIST'G	EXIST. CONC. BLK. (PAINT) NEW CONC. BLK. (PAINT)	ACoust. TILE (TYPE 3)
F2	EXIST'G FLOOR FIN. TO REMAIN	EXIST'G BASE TO REMAIN	EXIST. CONC. BLK. (PAINT) NEW BRICK TO MATCH EXIST'G	ACoust. TILE, COORD. W/ SPECS (TYPE 1)
F3	EXIST'G FLOOR FIN. TO REMAIN	EXIST'G BASE TO REMAIN	EXIST'G FIN. TO REMAIN	EXIST'G TO REMAIN
F4	EXIST'G PORCELAIN TILE	EXIST'G BASE TO REMAIN	EXIST. CONC. BLK. (EPOXY PAINT) NEW BRICK TO MATCH EXIST'G	EXIST'G TO REMAIN

FINISH SCHEDULE NOTES
① SEE SECTIONS/DETAILS

DOOR SCHEDULE									
NO.	TYPE	SIZE	MAT'L	GLASS	FRAME	THRESH.	WEATHER-STRIPPING	REMARKS	
101	A	3'-0" x 6'-8" x 1 3/4"	FRP	8'x24"	8 3/4" MET.	1/4"	YES	NO	RECESSED MARBLE THRESH.
102	A	3'-0" x 6'-8" x 1 3/4"	FRP	8'x24"	8 3/4" MET.	1/4"	YES	NO	RECESSED MARBLE THRESH.
103	A	3'-0" x 6'-8" x 1 3/4"	FRP	8'x24"	8 3/4" MET.	1/4"	YES	NO	RECESSED MARBLE THRESH.

PREPARE EXIST'G FLOOR EACH SIDE OF DOOR 102, WHERE WALL IS REMOVED TO RECEIVE MARBLE THRESHOLD.

