



TOILET ACCESSORY SCHEDULE								
TAG NO.	DESCRIPTION	MANUFACTURER	MODEL	FURNISHED BY		INSTALLED BY		COMMENTS
				CONTRACTOR	OWNER	CONTRACTOR	OWNER	
TA-A-01	1-1/2" DIA, 36 x 42 ADA GRAB BARS	BOBRICK	B-6806x36; B-6806x42	X		X		
TA-B-01	WALL MOUNTED SOAP DISPENSER	BOBRICK	B-2013	X		X		SOAP DISPENSER MUST ACCEPT FOAMING SOAP CARTRIDGE.
TA-C-01	PAPER TOWEL DISPENSER	GEORGIA PACIFIC	59460A	X		X		MUST ACCEPT 10" BY 800-FOOT PAPER TOWEL ROLLS. VERIFY WITH OWNER BATTERY OPERATED POWER METHOD.
TA-D-08	CHANNEL-FRAME MIRROR 24x36	BOBRICK	B-165 2436	X		X		
TA-E-01	TOILET TISSUE DISPENSER - SURFACE MOUNTED	BOBRICK	B-2890	X		X		MUST COMPLY WITH 10" DIA, 4" , 3" CORE DIA TOILET PAPER ROLL.
TA-F-01	SURFACE-MOUNTED SANITARY NAPKIN DISPOSAL	BOBRICK	B-254	X				MUST ACCEPT HEALTH GARD HS 6141 WAXED LINERS.
TA-G-01	TRASH RECEPTACLE, 16 GALLON	SIMPLEHUMAN	H-8672	X		X		
TA-H-01	DOOR HOOK - PER DOOR HARDWARE; A-4.01			X				TOP OF HOOK TO BE MOUNTED AT 48" AFF MAX
TA-H-02	SURFACE-MOUNTED MOP AND BROOM HOLDERS	BOBRICK	B-223 X 24	X		X		

FINISH SYMBOL LEGEND

- WALL FINISH (P-3B, B-7)
- BASE FINISH (P-3B, B-7)
- FLOOR FINISH (CPT-4)
- ACCENT WALL FINISH (P-4)
- FLOOR TRANSITION
- FINISH PLAN KEY NOTES (F#)
- FLOOR FINISH DIRECTION

KEY NOTES - FINISH PLAN

IF-1	TRANSITION FROM SEALED CONCRETE TO LVP
IF-1.1	TRANSITION FROM EXTERIOR CONCRETE TO LVP
IF-2	TRANSITION FROM LVP TO TILE FLOOR
IF-3	PEG BOARD, B.O.D. PROWOOD SKU #109089. INSTALL BLOCKING AS REQUIRED. 24" W x 48" H BOARDS INSTALLED 34" AFF.
IF-4	INSTALL CORNER GUARDS PER DETAIL 31D-1.01.
IF-5	INSTALL NEW WINDOW BLINDS AT ALL EXTERIOR WINDOWS AND EXTERIOR DOORS WITH LITES. PLEASE, SEE ID-1.01 FOR SPECIFICATION, WB-1.
IF-6	UNLESS NOTED OTHERWISE IN PLAN, INSTALL FLOOR TILE, METAL COVE TRIM, AND WALL TILE AS SCHEDULED ON ALL WALLS.
IF-7	UNLESS NOTED OTHERWISE IN PLAN, INSTALL RUBBER BASE, RB-1, WITH FRP-1 UP TO 48" ABOVE RUBBER BASE. USE DETAIL 41D-1.01. USE MANUFACTURER RECOMMENDED J CAP TO FINISH EXPOSED FRP EDGE. PAINT P-1 ABOVE.
IF-8	PRIME AND PAINT STEEL PORTION OF EXISTING METAL STAIRS. SEE ID-1.01 FOR PAINT COLOR.
IF-9	GC TO PROVIDE IN WALL BLOCKING FOR ALL WALL MOUNTED DIGITAL DISPLAY SCREENS/TVS.



208 Pirkle Ferry Road, Suite C
Cumming, GA 30040



FOCO FIRE STATION 15 RENOVATIONS

FORSYTH COUNTY

1525 BUFORD HWY
CUMMING, GA

PRINT RECORD

[illegible]

Drawn By HS
Checked By JDG

Date	Job No.
08/01/2025	25018

Sheet Title

FINISH & REFERENCE PLAN - LEVEL 1 & LEVEL 2

Sheet No.

ID-2.01

RELEASED FOR BID